


Location SW NW SE/4

Sec. 36 T. 24 R. 10E.

Casing Record

10" 909	Farm- Charles Lozier	No. 2	County- Greenwood.
20" 8 1/2" 1165	Company- Independent Oil & Gas Co.		
15 1/2" 65/8" 1825	Contr.- Harry Gore.		
12 1/2" 45 SIM 53/16"	Comm.- 11/20/1929.	Comp.- 12/8/1929.	
Total Depth 2079'	Shot Quarts Between		



Correspondence Regarding This Well Should Be Referred to

Elevation

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued 12/28/1929.

Formation	Depth	Formation	Depth
clay yellow sft	35	shale white sft	1450
lime white hrd	40	lime white hrd	1460
lime white hrd	45	shale blue sft	1465
slate blue sft	50	lime white hrd	1470
lime white hrd	55	sdv shale gray sft	1490
slate drk sft	65	slate blue sft	1500
slate drk sft	90	shale white sft	1555
lime drk hrd	95	lime white hrd	1570
shale drk sft	120	shale white sft	1585
lime white hrd	130	lime white hrd	1600
slate blue sft	140	shale white sft	1604
slate blue sft	180	lime white hrd	1625
lime white hrd	200	shale white sft	1675
slate blue sft	280	lime white hrd	1685
lime white hrd	308	shale white sft	1700
slate blue sft	313	lime white hrd	1735
lime white hrd	320	shale gray sft	1737
lime white hrd	330	lime white hrd	1746
lime white hrd	335	shale white sft	1790
slate blue sft	355	shale sdv drk sft	1825
lime white hrd	377	shale sdv black sft	1837
slate blue sft	380	shale sdv gray sft	1852
lime white hrd	394	sand gray sft	1858
shale gray sft	425	Show of oil 1852-1858'	
lime white hrd	435	sdv shale gray sft	1870
slate white sft	465	shale black sft	1931
lime white hrd	470	sdv shale gray sft	2000
slate blue sft	490	sdv shale gray sft	2025
lime white hrd	540	shale black sft	2074
shale gray sft	555	lime gray hrd	2079
shale gray sft	570	HFW 2079'	
sdv shale gray sft	580	TD	2079'
2 BW 570-580'			
lime white hrd	600		
slate white sft	610		
lime white hrd	645		
slate blue sft	668		
lime white hrd	671		
lime white hrd	680		
slate white sft	750		
shale white sft	835		
slate white sft	880		
lime white hrd	885		
sand gray sft	905		
HFW 885-905'			
10 BW 909-25			
shale gray sft	965		
slate blue sft	975		
lime white hrd	990		
HFW 935'			
slate white sft	997		
lime white hrd	1030		
slate white sft	1044		
lime white hrd	1130		
slate white sft	1170		
slate white sft	1280		
lime white hrd	1290		
shale white sft	1300		
lime white sft	1305		
shale white sft	1320		
lime white hrd 1BW 1380	1385		
shale gray sft	1392		
lime gray hrd	1415		
shale gray sft	1420		
lime gray hrd	1445		