

UNION NATIONAL BANK BLDG, WICHITA, KANSAS


Location. SW cor NE

Sec. 10 T. 24 R. 8E

Casing Record.

10" 662 Farm. Burk No. 1
 20" 8 1/4" 1454 Company. Ward McGinnis.
 15 1/2" 65/8" 2296'3 Contr.
 12 1/2" 53/16" Comm. 2-6-32 Comp. 2-27-32
 Total Depth. 2457 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.

County. Greenwood.



Figures Indicate Bottom of Formations.

Elevation.

Date Issued. 3-26-32

Initial Production

| Formation | Depth | Formation | Dry. Depth. |
|--------------------|-------|------------------------------|----------------|
| soil | 3 | lime hard light | 970 |
| gravel | 10 | shale light | 990 |
| lime | 30 | lime hard | 1000 |
| slate blue | 40 | lime | 1015 |
| slate blue | 50 | shale | 1050 |
| lime | 55 | lime | 1060 |
| slate blue | 70 | shale | 1080 |
| lime | 75 | lime | 1085 |
| slate | 80 | lime hard white | 1130 |
| lime | 90 | lime | 1140 |
| slate | 100 | shale light | 1185 |
| lime | 105 | slate white | 1190 |
| shale blue | 115 | shale light | 1200 |
| lime | 135 | sand broken water | 1210 |
| shale blue | 150 | sand water | 1239 HFW |
| lime | 170 | shale light | 1255 |
| shale white | 205 | lime rotten | 1285 |
| shale light | 215 | shale blue | 1310 |
| lime light | 220 | shale blue | 1360 |
| slate blue | 250 | shale blue | 1380 |
| lime blue | 255 | sand water | 1390 |
| shale blue | 265 | shale sdy | 1405 |
| red rock | 270 | lime | 1410 |
| lime | 275 | slate white | 1420 |
| shale brown | 290 | sand | 1435 |
| lime light | 295 | lime white | 1440 |
| shale light | 305 | lime | 1495 |
| shale light | 310 | lime white 1 1/2 BWPHR | 1565 |
| lime | 320 | shale | 1570 |
| shale | 360 | lime | 1585 |
| lime sdy wtr | 370 | shale big | 1675 |
| shale and shells | 440 | shale light | 1715 |
| shale blk | 445 | lime Oswego | 1750 |
| lime broken blk | 465 | slate | 1755 |
| lime hard blk | 490 | lime 1 BWPHR 1800 | 1815 |
| shale blk | 510 | lime Oswego 2 1/2 BWPHR 1870 | 1870 |
| lime light | 550 | lime Oswego | 1905 |
| shale | 570 | shale | 2015 |
| shale light | 580 | lime | 2040 |
| lime light | 585 | shale | 2050 |
| shale | 600 | shale shelly | 2100 |
| lime broken | 645 | lime hard | 2115 |
| sand water HFW | 655 | hole caving bad at 2065. | |
| lime hard | 660 | lime and shale | 2180 |
| shale blue | 695 | hole caving bad 2165-2175 | |
| lime light | 705 | shale and shells | 2190 |
| shale blue | 710 | slate and shells | 2220 |
| shale | 715 | fighting cave. | |
| lime | 735 | shale and shells dark | 2284 |
| slate white | 760 | shale dark | 2314 |
| lime light 1 BWPHR | 810 | broken sand | 2337 |
| shale light | 825 | red rock Hole caving. | 2342 |
| lime hard | 830 | slate | 2395 |
| shale | 845 | shale | 2457 |
| shale | 855 | T.D. | |
| lime | 880 | | |
| slate white | 900 | | |
| lime hard | 915 | | |
| sand water 8 BWPHR | 925 | | |
| lime | 935 | | |
| shale blue | 945 | | |
| lime light | 950 | | |
| shale light | 955 | | |