


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE WESTERN KANSAS OIL & REFG. CORP ET AL.
Keagy No. 1.

SEC. 15 T. 25 R. 1E.
NW SE SW

Total Depth. 3398
Comm. 4-18-36 Comp. 2-8-37
Shot or Treated.
Contractor.
Issued. 3-20-37

County Sedgwick.



CASING. 30
20" 34' 65/8" 2913'
15 1/2" 254' UR 3163'
133/8" 1047' 53/16" 3375'
10" 1762'
8" 2395'

Elevation. 1439

Production. Pot. 377 B.

Figures Indicate Bottom of Formations.

sdv shale	15	lime	1075	S.S.O. 2240	
shale	75	shale	1115	shale	2255
3 BW 55-65		lime	1120	lime	2270
shale	80	shale	1150	shale	2275
lime shells	82	lime	1158	lime	2290
shale	150	shale	1190	shale	2305
lime	160	lime	1195	lime	2360
shale	170	shale	1285	sdv lime	2367
limo	175	5 BWPHR 1230-1240		lime	2465
shale	180	lime	1290	shale	2519
lime	190	shale	1325	lime	2530
shale	205	lime	1335	sdv lime	2538
lime	215	shale	1360	S.S.O. 2532-2536	
shale	225	lime	1365	lime	2552
limo	235	shale	1375	shale	2558
shale	250	lime	1425	lime	2573
lime	280	shale	1430	Inc. Oil 2560-2563	
shale	300	lime	1435	shale	2575
lime	310	shale	1440	lime	2604
shale	315	lime	1460	inc. oil 2580-2582	
lime	380	shale	1465	shale	2607
lime and s hale	400	lime	1490	lime	2629
shale	410	shale	1500	inc. oil 2616-2619	
red rock	415	lime	1505	sand	2635
shale	420	shale	1545	2 BW 2629-2635	
limo	435	shale lime	1560	lime	2660
shale	475	lime	1607	shale	2665
red rock	480	shale	1665	lime	2690
lime	545	lime	1695	broken lime	2695
shale	550	shale	1700	lime	2700
lime	615	lime	1725	sdv lime	2717
sdv lime	630	sand	1735	shale	2770
shale	635	HFW 1725-1735		lime	2812
lime	650	shale	1758	shale	2838
shale	655	lime	1777	lime	2850
lime	680	shale	1782	lime shell shale	2875
shale	690	lime	1787	shale	2880
sdv lime	715	shale	1835	lime	2890
lime	725	lime	1845	2890 equals 2913 corrected.	
shale	735	lime shale	1875	broken lime	2918
red rock	740	lime	1960	lime	2925
shale limo	765	6 BWPHR 1900		shale	2947
lime	800	shale	1995	limo	2950
shale	815	lime	2030	shale	2953
lime	825	shale	2045	lime	2957
shale limo	865	broken lime	2050	shale	2959
lime	880	lime	2080	lime	2965
shale	890	shale	2090	shale	3000
shale limo	915	lime	2095	chat	3005
lime	950	shale	2140	show oil 3000-3003	
shale blk	955	lime	2150	lime	3032
shale	965	shale	2155	Var. col. shale and	
lime	985	lime	2165	shells	3050
sdv lime 8BW 985-995	1005	shale	2200	broken lime	3058
lime	1035	lime	2215	lime	3062
15 BWPHR 1010-1025		shale	2225	chat lime	3070
lime	1050	lime	2230	lime	3080
shale	1070	sdv lime	2245	sand	3085

OVER

Western Kansas, et al.

Keagy No. 1. 15-25-1E.

4 BW 3050-3058

14 BWPFR 3080-3085

sand 3095

lime 3109

red and green shale 3111

broken lime 3122

S.S.O. 3111-3113

lime 3261

shale 3265

lime 3310

shale 3317

lime 3319

shale 3389

lime 3390

3390 equals 3397 corrected.

sand lime

lime 3398

Total Depth.

Pay 3396-3398

1000' oil 10 hrs.

2200' oil 36 hrs.

casing collapsed on this well. Rotary was moved in and
hole side tracked at 2000 feet.

New hole.

53/16" casing at 3375

Top Dolomite 3378

Total Depth. 3379

Potential 377 B.

Completed Feb. 8, 1937