



Home Office: Great Bend, Kansas
P.O. Box 393 Gladstone 3-7903

COMPANY O. A. Sutton WELL Buzzi #3
DATE 7-17-61 COUNTY Sedgwick STATE Kansas
TEST NO. 1 TICKET NO. 9549 K TYPE TEST open hole (conventional)
TEST APPROVED BY R. K. Grant WESTERN REPRESENTATIVE Paul I. Engler

TEST DATA:

Tested From 3443' To 3451' Depth 3451' T.D.
Hydrostatic Mud Pressure—Initial (A) 1800# Final (B) 1800#
Flow Pressure—Initial (B) 100# Final (C) 585#
Bottom Hole Pressure—Initial (F) 955# Final (D) 940#
Tool Open 1 Hr. - Min.; Shut-in-Initial - Hr. 30 Min.; Shut-in-Final - Hr. 30 Min.
Chokes; Surface 1/2" Bottom 3/4" Fluid Cushion: Type None Amount None
Recovery:

810' Free Oil	On Bottom	⊙	9:50
660' Sulfur Water	I.S.I.P.	⊙	9:52
	Tool Open	⊙	10:22
	F.S.I.P.	⊙	11:22

SURFACE DATA:

BLOW: Good throughout test


Maxium Surface Pressure None Did Well Flow? No

Description of Flow	Time	Max. Pressure	Size Surface Choke

GENERAL OPERATIONAL DATA:

Hole Size: Main Hole 7 7/8" Rat Hole None Drill Pipe Size 4 1/2" F.H.
Hole Condition O.K. Mud Weight 10.2 Viscosity 42
Type Pressure Recorder Western Recorder No. 59 and 60 Date Calib. 2-28-61
Extra Equipment: Dual Packer Yes Jars No Safety Joint No
Was Test Recovery Reversed Out? No Bottom Hole Temperature 120°
Number of Copies Requested Five

REMARKS:

O. A. Sutton
Buzzi #3Test #1
T.K.T. # 9549-K

This is an actual photograph of recorder chart.

PRESSURE DATA

A) Initial Hydrostatic Mud	1800#
B) Initial Flow	100#
C) Final Flow	585#
D) Final Shut-In	940#
E) Final Hydrostatic Mud	1800#
F) Initial Shut-In	955#

Point

Pressure

Cal/2 W/2 N41 Sec. 32-25-1E
Delaware Co, Pa