

Kilby Drilling Co., Inc.

DRILLING AND CORING CONTRACTING

ROTARY TOOLS

316-625-2366
Center, Kansas 66783

Company - Richard A. Soule
Farm - Smith "D"
Well No. - 1
Drlg. Comm. - June 3, ±985
Drlg. Comp. - June 7, 1985
API# - 15-073-23,428
107' 8 5/8" surface set w/50 sks. cement / 3% CaCl.

Location
Greenwood County, Kansas
Sec. 31 Twp. 25 Rge. 11E

Figures indicate formation tops:

Formation	Depth
Soil	0
Lime	6
Shale	8
Lime	69
Shale	83
Lime	163
Shale	198
Lime	208
Red Bed	249
Shale	267
Lime	297
Shale	304
Lime	324
Shale	328
Lime	402
Shale	419
Lime	469
Shale	478
Lime	484
Soft Lime	512
Lime	549
Shale	562
Lime	785
Shale	787
Lime	906
Shale	984
Lime	1193
Shale	1203
Lime	1218
Shale	1224

Continued

Formation	Depth
Lime	1252
Sand	1285
Lime	1298
Shale	1317
Lime	1324
Shale	1419
Lime	1501
Shale	1505
Lime	1531
Shale	1547
Lime	1595
Shale	1680
Lime	1759
Shale	1762
Lime	1901
Shale	1902
Top Miss. Lime	2034
Break	2044
Lime	2051
Break Odor	2068
Lime	2981
T.D. Rotary	2105
Completed dry	

Hole filled with heavy drilling mud
Drill pipe ran to 2105 ft.
15 sks. cement pumped at 2105 ft
Drill pipe pulled to 700 ft.
15 sks. cement pumped at 700 ft.
Drill pipe pulled to 160 ft.
Cement pumped from 160 ft. to GL
All cement mixed and pumped by
Sun Cementing Co.
June 7, 1985 7:35p.m.