

0-- 2'-soil
 2'-- 12'-grey clay
 12'- 28'-brown-yellow clay
 28'- 31'-yellow clay w/gravel
 31'- 42'-lime
 42'- 43'-coal
 43'- 88'-blu shale
 88'- 164'-sandy blu shale w/lime lenses
 164'- 167'-sandy grey lime
 167'- 183'- blu shale
 183'- 189'-hard dark grey lime
 189'- 210'-broken sandy lime soft
 210'- 357'-blu shale w/lime lenses
 357'-374' -blue shale
 374'- 500'-lime
 500'- 568'-broken lime w/blu shale lenses
 568'- 579'-blue shale
 579'- 640'-light grey lime soft
 640'- 674'-broken lime w/blushale lenses
 674'- 683'-blu shale
 683'- 686'-lime
 686'- 690'-blu shale w/lime lenses
 690'- 692'-blk.shale
 692'- 778'-lime
 778'- 783'-sandy lime hard
 783'- 791'-sand oil show 783'-787'
 791'- 824'-lime sandy
 824'- 839'-broken lime w/shale lenses
 839'- 847'-blu shale
 847'- 850'-lime dark grey
 850'- 916'-blu shale
 916'- 921'-broken lime w/ blu shale lenses
 921'- 952'-blu shale
 952'- 955'-black slate
 955'- 979'-blu-brown shale
 979'- 982'-lime
 982'- 987'-broken lime
 987'- 997'-blu shale
 997'-1089'-broken lime w/blu shale lenses
 1089'-1020'-lime lt. grey
 1020'-1032'-black shale
 1032'-1036'-lime
 1036'-1051'-blu shale lime lenses
 1051'-1088'-blu shale
 1088'-1092'-lime
 1092'-1096'-broken lime
 1096'-1097'-coal
 1097'-1108'-lime
 1108'-1115'-blu shale
 1115'-1117'-lime
 1117'-1120'-blu shale
 1120'-1122'-broken lime
 1122'-1124'-coal
 1124'-1138'-blu-brown shale
 1138'-1157'-lime
 1157'-1159'-blu shale lime lenses
 1159'-1162'-black shale
 1162'-1170'-blu shale
 1170'-1197'-sandy blu shale w/black shale lenses
 1197'-1202'-sandstone soft oil show
 1202'-1204'-sandstone w/clay lenses, light oil show

State of Kansas, Woodson County
 John S. Morris, own Tools
 Anna Laura McNitt Farm-well # 6
 NE 1/4 S.20-T.25-R.14

Casing Record-
 7" set @ 112' cemented
 4 1/2" set @ 1370' cemented w/40 sks.
 by Consolidated

1204'-1206'-sandstone firm,hard
 1206'-1209'-shale
 1209'-1216'-sandstone firm
 1216'-1342'-shale
 1342'-1347'-sand firm,oil show
 1347'-1359'-sand soft,good oil show
 1359'-1370'-sandy shale
 T.D.-1370'

20-25-14E

