

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 18 T. 25 R. 16E E
W

API No. 15 — 207 — 20,755
County Number

Loc. SE NW SE

County Woodson

Operator Tec Drilling Co., Inc.

Address Post Office Box 693, El Dorado, Kansas 67042


Well No. #2 (SC) Lease Name Tommy Kee

Footage Location 1650 feet from (S) line 2280 feet from (E) line

Principal Contractor B & F Drilling Co. Geologist None

Spud Date May 21, 1974 Total Depth 1043 P.B.T.D.

Date Completed May 23, 1974 Oil Purchaser MacLaskey Vacuum Transport



Locate well correctly
Elev.: Gr. 1037

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	6"	5½"	20	43'	portland	7	none
Oil string	3½"	2-7/8"	6	1039'	portland	125	none

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			
1"	1004'	none	2	½" coneshots	1004-1009

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture: 200 bbls lease crude 11,500# 10-20 sand	
1,000# 12-30 sand	
1 barrel HCl acid	1004-1009

INITIAL PRODUCTION

Date of first production 5-29-74	Producing method (flowing, pumping, gas lift, etc.) pumping
RATE OF PRODUCTION PER 24 HOURS	Oil ten bbls. Gas trace MCF Water trace bbls. Gas-oil ratio very low CFPB
Disposition of gas (vented, used on lease or sold) vented	Producing interval (s) 1004-1009

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Tec Drilling Co. Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

2 SC

Lease Name

Tommy Kee

oil

S 18 T 25 S R 16 E

SW/NW/SE

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & clay	0	22		
Shale	22	100		
Lime	100	146		
Shale	146	151		
Lime	151	168		
Shale & red bed	161	192		
Lime	192	398		
Sand	398	435		
Shale	435	486		
Lime	486	541		
Shale-black	541	546		
Lime	546	578		
Shale - black	578	581		
Lime	581	601		
Shale	601	763		
Lime	763	768		
Shale	768	772		
Lime	772	798		
Shale	798	806		
Sand	806	820		
Shale-sandy	820	873		
Lime - brown	873	876		
Shale	876	881		
Lime	881	908		
Shale - black	908	912		
Shale	912	925		
Lime	925	946		
Shale	946	951		
Lime	951	953		
Shale	953	957		
Shale - sandy	957	969		
Shale	969	1001		
Cap rock	1001	1002		
Sand (cored 1002 - 1016)	1002	1009		
Shale	1009	1043 TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

