

# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

April 2, 1981

Sheedy Oil Group, Inc.  
Box 269  
Yates Center, Kansas 66783

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the L. C. Chambers B Lease, Well No. 1, located in Section 19, T-25S, R-17E, in Woodson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on March 28, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES



Sanford A. Michel

SAM/kas

4 c to Yates Center, Kansas  
1 c to Chanute, Kansas

**OILFIELD RESEARCH LABORATORIES**

LOG

Name Sheedy Oil Group, Inc. Lease L. C. Chambers B Well No. 1

Depth Interval,  
Feet

Description

SQUIRREL SAND

801.0 - 803.3 Brown and gray laminated sandstone and shale.

803.3 - 804.2 Brown sandstone.

804.2 - 808.4 Brown and gray laminated sandstone and shale.

808.4 - 808.8 Brown sandstone.

808.8 - 810.7 Brown and gray laminated sandstone and shale.

## Oilfield Research Laboratories

## RESULTS OF SATURATION &amp; PERMEABILITY TESTS

TABLE 1

Company Sheedy Oil Group, Inc. Lease L. C. Chambers B Well No. 1

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	801.6	14.2	31	46	77	342	5.0
2	802.5	5.7	52	13	65	230	Imp.
3	803.5	14.7	54	23	77	616	11.
4	804.5	14.8	60	33	93	689	1.6
5	805.5	13.2	33	52	85	338	3.3
6	806.5	11.3	44	38	82	386	0.47
7	807.5	11.2	38	47	85	330	0.49
8	808.5	15.7	37	30	67	451	26.
9	809.5	12.0	45	45	90	415	1.3
10	810.3	11.8	51	43	94	467	2.1