

WELL RECORD

JUL 14 1966

Well No. **29-I** Farm **Woodward** Producer **CRA, Inc.**
Location _____ Sec. _____ Twp. _____ Rg. _____
Elevation _____ State **Kansas** County **Bourbon**
Kind (Oil, Gas, Water, Dry Hole) _____ Contractor **Acc-HI Exploration Co.**
Producing formation _____ Top _____ Bottom _____
Shot with _____ qts. _____ from _____ to _____
Packer Set at _____ Kind _____ Size _____
Liner _____ from _____ to _____ Perforated from _____ to _____

LOG

Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
30'	Surface-line	30'	2	Shale	685
60	Lime	120	5	Blk. sand & oil	690
32	Shale	152	5	Blk. sand & sh.	695
24	Lime	176	15	Shale	710
94	Shale	270			
135	Lime-shales	405			
44	Shale	449			
44	Lime	493			
141	Shale	634			
4	Sand	638			
Core #1					
26.5'	(638-664.5)				
6.5	Gas sd. w/ sh. lam.	644.5			
2.5	Sdy. Shale	647			
5	Trans. zone gas to oil	652			
2	Oil Sand	654			
.2	Shale	654.2			
10.3	Oil Sand	664.5			
Core # 2					
18.5'	(664.5-683)				
11.5	Oil Sand	676			
6	Shale	682			
1	Bl. Sand	683			

Total Depth **710'**
Open Hole _____
Casing **8 5/8"** at **30'**
Casing _____ at _____
Casing **--run 690.81' of 4 1/2"**
cemented to top by Halliburton
Cement _____
Tubing _____
Rods _____
Additional Information _____
All measurements taken from
ground level.