

Marshall Number 2, Nov., 1918.

Northwest $\frac{1}{4}$, Sec. 5, Twp. 25 S., R. 23 E.

5-25-23E
33.3

Plotted

Blotted

	Thickness	Depth.
Soil	42	42
Brown limestone	8	50
Slate	42	92
Sand	8	100 Showing of oil.
Slate	42	142
Brown limestone	15	157
Dark slate	7	164
Brown limestone	8	172 Little gas.
Dark slate	23	195
Light slate	15	210
White limestone	18	228 75,000 cu. ft. gas.
Dark slate	8	236
Brown limestone	3	239
Coal	1 $\frac{1}{2}$	240 $\frac{1}{2}$
Light slate	7 $\frac{1}{2}$	248
Oil sand	14	262 Showing of oil; 75,000 cu. ft. gas.
Dark slate	58	320
Light slate	25	345
Dark slate	75	420
Light slate	20	440
Dark slate	29	469
Gas sand	7	476 50,000 cu. ft.
Dark slate	44	520
Broken s.	10	530
Dark slate	61	591
Gas sand	6	597 50,000 cu. ft.
Lime sand	23	620
Dark slate	5	625
Oil sand	15	640