

Company Southwestern Gas Company

Farm P. F. Piotrowski No. 1

Sec. 26 T. 25 R. 24E

Total Depth 409

Loc. 470½'E and 330'N of
SW corner

Comm. 7/25/28

Comp. 7/28/28

County Bourbon

Casing

Production Dry Plugged

8 1/2"

10'

6 1/2"

71'

Figures Indicate Bottom of Formation

Thickness

5	soil clay	5
3	boulders	6 fresh water at 9' 5 blrs.
5	shale blue	13
6	lime	19
7	shale black	26
1	coal	27
33	blue shale light	60
10	shale sandy	70
20	shale blue	90
22	shale dark	112
2	lime	114
5	shale dark	119
1	lime	120
10	shale blue	130
10	shale light	140
10	shale blue light	150
20	shale light	170
15	shale dark	185
30	shale light	215
9	shale dark	224
59	shale light	283 small show gas at 283
4	shale dark	287
3	shale light	290 small increase gas
10	shale dark	300 show oil 300'
25	sand	325
10	shale light	335 water 300-305 2 blrs.
32	shale dark	367 6 blrs. water 381'
5	shale light	372
37	lime Mississipp	409 H.F.W. 408'
	T.D.	409