

my  
Company Southwestern Gas Company

26-25-24E

Farm R. M. Givens No. 1

Sec. 26 T. 25 R. 24E

Total Depth 298

Loc. 990' E. and 330' S. of  
NW corner of SW $\frac{1}{4}$

Comm. Aug. 29, 1928 Comp. Sept. 1, 1928

County Bourbon

Casing 8 $\frac{1}{2}$ " 8'6"

Production 119,040 cu. ft.

Figures Indicate Bottom of Formation.

Thickness		Depth
7	boulders	7
5	black slate coal	12
1	light shale	13
5	lime	18
6	black slate	24
3	broken lime	27
8	black shale	35
35	light shale	70
18	dark shale	88
2	lime	90
4	black mud	94
3	black lime	97
15	black mud	112
2	lime	114
11	black mud	125
15	gray shale	140
20	black shale	160
15	gray shale	175
7	black shale	182
1	lime	183
12	black shale	195
8	shale grey	203
8	white mud	211
19	dark shale	230
8	light shale	238
5	sand dry	243
17	light shale	260
20	dark shale	280
3	black shale	283
2	broken sand	285 some gas
5	shale	290
4	sand	294 82,080 gas
2	sand	296 92,160 gas
1	sand	297 98,280
1	sand	298 119,040 gas after tubing.