



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

June 25, 1982

Town & Country Realtors
3 South Main
Ft. Scott, Kansas 66701

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Lewis Lease, Well No. 1, located in Section 26, T-25S, R-25E, in Bourbon County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on June 24, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/dlb

5 c to Ft. Scott, Kansas

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name Town & Country Realtors Lease Lewis Well No. 1

<u>Depth Interval, Feet</u>	<u>Description</u>
---------------------------------	--------------------

WARNER SAND

204.0 - 205.0	Brown sandstone with scattered micaceous partings.
205.0 - 206.0	Brown sandstone.
206.0 - 207.0	Brown sandstone with scattered micaceous partings.
207.0 - 207.8	Brownish black sandstone.
207.8 - 212.0	Gray shale.
212.0 - 215.0	Gray slightly sandy shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Town & Country Realtors Lease Lewis Well No. 1

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	204.5	19.9	47	20	67	726	18.
2	205.5	21.0	52	21	73	847	24.
3	206.5	21.5	65	12	77	1084	21.
4	207.5	20.0	51	29	80	791	63.