

24-25-25E

Kilgren Oil Co.

Wolfe No. 1

center 24-25-25

Bourbon County, Kansas

drld. August, 1947

Total Depth 459 ft.

Elev: 775
topo

small oil well, produced 150 bbls then abandoned

river soil, wood	0	37	water
sandy shale	37	43	
shale	43	58	
coal	58	59	
shale	59	80	
limey sand	80	85	
shale	85	90	
dark shale	90	100	
shale, sandy	100	116	
sandstone, hard	116	144	
sand, shaley	144	155	
sand	155	194	gas
shale, sandy	194	200	
shale, dark	200	209	
sand, tight	209	214	gas and oil
chat	214	227	heavy oil
lime, hard	227	277	
lime, soft	277	285	
lime and flint	285	430	
shale, green	430	459	TD

Harold Kilgren
Yates Center, Kansas