

WELL & LOCATION: CSO No. 209 Wilson 8 253 SE BU Co.

[illegible]

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY,
412 Union National Bank Bldg, Wichita, Kansas.


CITIES SERVICE OIL CO.
Wilson No. 209

SEC. 8 T. 25 R. 5.E
SW NW SW NW
890' N 330' E of W $\frac{1}{2}$ Cor.

Total Depth. 2036 $\frac{1}{2}$
Comm. 11-23-41 Comp. 12-1-41
Shot or Treated.
Contractor. Hissom Drilling Co.
Issued. 2-14-42

County Butler.

K. G. S. LIBRARY



CASING.

66/8" 1972 cemented.

Elevation.

Production. 46 B.O.
33 B.W.

Figures Indicate Bottom of Formations.

surface shale	15
lime	50
lime and shale	1480
shy shale	1530
shale and lime	1590
shale	1695
lime	1771
lime and shale	1850
shale	1967
lime	1980
lime SLM	1979 $\frac{1}{2}$
lime	2036 $\frac{1}{2}$
Total Depth.	

Top Wakarusa lime 798'
Base Wakarusa 818'

Top Burlingame lime 831'
show oil 831-38
Sl. show oil 857-60
Base Burlingame 868

Top Lansing lime 1695
show oil 1733-56
Base Lansing 1859

Top Kansas City 1967'
show oil 1975-88; 1996-2015;
2019-36 $\frac{1}{2}$;

Note - Fillup 1 bbls oil and 6 gal water per hr
(8D $\frac{1}{2}$ hr 25 gal. oil and 3 gal. water.

Acidize 2000 gal.

I.P. 46 bbls oil and 33 bbls water.
Av. 2nd 5 D.T.(after acid)