

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD.

LOCATION 330' fr NL 330' fr WL  
 NW cor NE.

SEC 13 T 25 R 8 E.

10" 1125 FARM Welch  
 20" 8 1-4 1515 COMPANY Roth & Faurot.  
 15 1-2 6 5-8 2291 CONTRACTOR  
 12 1-2 404 5 3-16 2430 COMMENCED May 7, 1926.

NO. 1 COUNTY Greenwood



TOTAL DEPTH

COMPLETED July 19, 1926.

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION

INITIAL PRODUCTION 60 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 8/20/26

Formation	Depth	Formation	Depth
cellar	5	lime	2110
slate	30	slate	2125
lime	75	water sand (3 BWPB)	2165
slate	100	slate	2170
lime	150	lime	2180
slate	175	slate	2260
lime	200	water sand	2265
slate (12 1/2" csg. set in)	397	shale (6 5/8" set in)	2300
lime (lime at 398-2)	410	(shale at 2268-9)	
slate	430	sand (no water)	2330
lime	460	slate	2370
slate	465	broken slate & sand	2380
lime	470	(no water nor oil)	
shale	500	black slate	2395
lime	510	black slate shell	2402
shale	520	(5 3/16" set in sand 2405')	
lime	560	Bart. oil sand	2445
slate	720	(300' of oil in hole at time)	
lime	740	(casing was set.)	
slate	790	black slate	2450
lime	850		
slate	900		
lime	925		
slate	1020		
lime	1035		
shale	1100		
lime (10" csg. set in lime)	1160		
slate (114-2)	1170		
sand	1195		
slate	1250		
sand (HFW at 1235')	1330		
slate	1410		
sandy lime	1490		
big lime	1635		
(8 1/4" csg. set in big lime at)			
slate (1498-6)	1790		
Oswego lime	1890		
slate	1910		
Oswego lime (1 BWPB)	1965		
slate	2050		
lime shell	2060		
slate	2090		