

WILSON

LEASE

260

1

CITIES SERVICE OIL COMPANY

ELDORADO, KANSAS

DISTRICT

LOCATION 9-25-5

FIELD Eldorado

COUNTY Butler

STATE Kansas

CONTRACTOR White & Ellis Drill-
ing Co.
MUD DATA

Kind Chemical

Weight 9.7 lbs.-gal.

Viscosity 35 Sec.

Filter Loss - c. c. Filter Cake - in.

Est. Gauge Depth Temp. 100 F°

Time Tool Open 1 Hour

Time Closed In. 15 Minutes

Depth BT. Gauge 2401' Ft.

BT. PRD. No. 396 Blanked Off No

12 Hr. Clock No. 948

Pressure Readings Field Office Corrected

Initial Hydro Mud Pressure 1217 p.s.i.

Initial Flow Pres. 11 p.s.i.

Final Flow Pres. 34 p.s.i.

Closed in Pres. 531 p.s.i.

Final Hydro Mud Pressure 1205 p.s.i.



OIL WELL CEMENTING CO.

HOLE AND TOOL DATA

Total Depth	2425'	Casing Perforations	Top	Bottom	Kind of Job	Open Hole
Top Packer Depth	2409'	Bottom Packer Depth	-	-	Price	\$215.00
Casing or Hole Size	8 3/4"	Liner or Rathole Size	-	-	Second Packer Assembly	-
Formation Tested	Viola				Safety Joint	-
Size Drill Pipe	3 1/2"	Size Drill Collars	5	3/4" x 60'	Extra Folder Charge	-
Size Bottom Choke	1 1/2"	Size Surface Choke	1 1/2"		Jars	-
Size Hook Wall Packer	-	Size Rings	-	No. Rings	Total	\$215.00
Size D. E. Wall Packer	7 1/2"	No. Packers	1		Witnessed By	Beyer
Size & Length Anchor	3 1/2" x 16'				Tester	Folmsbee
PRD Device No.	1691	Depth	2425'	Blanked Off	Yes	

REMARKS: Tool opened with a very weak blow that died in 5 minutes. By passed tool in 30 minutes. Recovered 63' (5' oil and 58' oil cut mud).

Amount of Cushion None All depths measured from Kelly Bushing No. Folders Reproduced 3

9-25-54

60924

~~60924~~

WILSON

LEASE

260

2

WELL NO.

TEST NO.

CITIES SERVICE OIL COMPANY

COMPANY

ELDORADO, KANS

DISTRICT

LOCATION 9-25-5

FIELD Eldorado

COUNTY Butler

STATE Kansas

CONTRACTOR White & Ellis Drill-
ing Co.
MUD DATA

Kind Aquagel

Weight 9.7 lbs.-gal.

Viscosity 34 Sec.

Filter Loss - c. c. Filter Cake - in.

Est. Gauge Depth Temp. 100 F°

Time Tool Open 30 Minutes

Time Closed In. 15 Minutes

Depth Bt. Gauge 2452' Ft.

Bt. P.R.D. No. 297 Blanked Off No

12 Hr. Clock No. 1552

Pressure Readings Field Office Corrected

Initial Hydro Mud Pressure 1231 p.s.i.

Initial Flow Pres. 22 p.s.i.

Final Flow Pres. 193 p.s.i.

Closed in Pres. 541 p.s.i.

Final Hydro 1007



OIL WELL CEMENTING CO.

HOLE AND TOOL DATA

Total Depth 2470'

Top Packer Depth 2450'

Casing or Hole Size 8 3/4" Liner or Rathole Size -

Formation Tested Simpson

Size Drill Pipe 3 1/2" Size Drill Collars 6 3/4"

Size Bottom Choke 5/8" Size Surface Choke 1/4"

Size Hook Wall Packer - Size Rings - No. Rings -

Size D. E. Wall Packer 7 1/2" No. Packers 1

Size & Length Anchor 3 1/2" F.J. x 20'

PRD Device No. 1860 Depth 2470' Blanked Off Yes

REMARKS: Tool opened with a strong blow. Recovered

145' slightly oil and gas cut mud, 120' muddy water,
and 120' water.

Date 1-30-54

Ticket No. 14474

HOW CO DISTRICT Winfield

Kind of Job Open Hole

Price \$215.00

Second Packer Assembly -

Safety Joint -

Extra Folder Charge -

Fars -

Total \$215.00

Witnessed By G. W. Geyer

Tester Joe Oliver

