

JUN 27 1970

D. S. SANDLIN DRILLING CO.
BOX 232 IOLA, KANSAS

25-26-12E
COPY

25-26-2F

SW SE SW

TO: WARD MCGINNIS
FARM MCGINNIS, FEE
APRIL 1968
GREENWOOD COUNTY, KANSAS
WELL 2B *Mc Innis "B"*

HICKNESS	FORMATIONS	TOTAL DEPTH
8	soil an clay	8
3	red bed	11
9	lime shells	20
14	sand w/lime st	34
20	shale	54
6	lime	60
30	shale	90
13	lime	103
55	shale w/lime st	158
12	lime	170
38	shale w/ lime st	208
2	sand	240
66	sandy shale w/lime	306
21	shale	327
18	lime	345
35	shale	480
3	lime	490
15	lime w/ shale	505
55	lime	560
8	shale	568
67	lime	635
103	shale	738
12	lime	750
50	sandy lime	800
10	lime w/ shale st	810
3	sandy lime	820
20	shale	840
66	lime	906
9	sandy lime	915
24	lime	939
4	black shale	943
39	lime	982
4	black shale	986
1	lime	1010
18	shale w/ lime st	1028
27	lime	1055
15	lime w/ shale st	1070
5	shale	1115
	shale w/ lime	1120
12	lime	1132
13	sandy lime	1145
10	lime	1155
145	shale w/lime st	1301
4	black shale	1305
59	sandy shale	1366
4	lime sandy	1370
242	sandy shale	1612
188	lime	1800
88	dark lime w/ shale st	1888
42	dark shale	1930
	sand broken	1941 T. D.

P 5 BOPD + inter
arb.

miss 1640
arb 1941

Set 306' of 7" surface pipe an
cemented w/ 100 sacks.
Set 1941' of 4" an cemented with
100 sacks, Baker shoe on bottom