

CORE

Pendley 6AD

22-26-14E

- 1228-1231.8 sh lt gry, brownish
- 1232.2 ss with v. fine, white, fair sal
- 1232.6 sh, lt gry
- 1232.85 ss, v. fine, white, fair sal
- 1233.2 sh, lt gry
- 1234. ss, fine, white, fair sal
- 1234.2 sh, lt gry
- 1241.1 ss, fine, white, fair sal
- 1243.5 sh, med-lt gry
- 1265 sh, med gry, white, fair sal

SPLES

1268 " " " "

CORE

1275.3 " " dk gry "

1301. sh, lt gry "

SPLES

1308 " med-lt gry

CORE

1308.8 sh, dk gry uniform

1314.1 sst, lt gry, interl w/ med

1316.8 sh, dk gry

1318.4 sst, lt gry, thin, interl w/ sh, dk gry

1319.9 sst, wh, ss, v. fine, med, gry, thinly interl.

1323.8 ss, fine, w/ good, med, sst w/ 10% med sst from f sh lam.

1326 sh, dk gry, white, med, sst fine

1326.4 ss, fine, w/ good, med, sst

1328.7 sh, dk gry, thinly interl w/ med sst

1330.6 ss, fine, med, sst

1332.5 sh, dk gry, white

1334.25 sst, lt gry, v. fine, med, sst, sh lam.

1334.8 sh, dk gry

- 1338.9 sst, wh, ^{interb} thinly interb w/ sh, dk gry
- 1339.4 ss, fn gr, good dead oil sat
- 1340.2 sh, dk gry, w/ occas thin wh int sst
- 1341.3 ss, fn gr, good dead oil sat
- 1341.7 sh, dk gry & thin lt gry sst
- 1346.5 ss, fn gr, good dead oil sat
- 1348.1 sh, dk gry, thinly interb w/ ss fn gr, 50:50, ss w/ dead oil sat
- 1361.7 ss, fn, L gr, good dead oil sat
- 1370. sh, blk, slicken, crinoid

Move from 1265' up for 1' adjustment -
 No correction for shale

Bottom shot @ 1239 }
 Top shot @ 1233 } 8 shots