



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

August 23, 1982

Energy Exploration & Production, Inc.
1012 Baltimore
Suite 600
Kansas City, Missouri 64105

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the O'Bryan Bloody Run Lease, Well No. 3, located in Section 36, T-26S, R-15E, in Woodson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on August 12, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/rmc

5 c to Kansas City, Missouri

- REGISTERED ENGINEERS -

ROCK ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Company Energy Exploration & Production, Inc. Lease O'Bryan Bloody Run Well No. 3

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
	<u>TUCKER SANDSTONE</u>
1038.0 - 1056.0	Brown sandstone.
1056.0 - 1058.5	Light brown sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Energy Exploration
 Company & Production, Inc. Lease O'Bryan Bloody Run Well No. 3

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. /A Ft.	Perm., Mill.
			Oil	Water	Total		
1	1038.5	22.8	40	20	60	708	1946.
2	1039.7	22.0	43	25	68	734	1239.
3	1040.7	21.1	43	22	65	704	695.
4	1041.5	23.0	47	20	67	839	1978.
5	1042.5	21.4	45	21	66	747	1251.
6	1043.5	23.4	47	12	59	853	2044.
7	1044.5	21.6	46	21	67	771	1393.
8	1045.4	22.8	48	20	68	849	1363.
9	1046.6	22.0	35	19	54	597	1572.
10	1047.4	23.1	43	22	65	771	1179.
11	1048.5	21.9	40	20	60	680	1115.
12	1049.5	22.6	40	23	63	701	1179.
13	1050.5	22.3	42	20	62	727	1393.
14	1051.7	21.7	35	25	60	589	1752.
15	1052.5	23.3	35	23	58	633	1858.
16	1053.5	23.4	32	23	55	581	1226.
17	1054.6	24.2	33	27	60	620	2114.
18	1055.4	23.8	17	53	70	314	1426.
19	1056.5	22.0	17	50	67	290	1393.
20	1057.5	23.0	16	53	69	286	829.
21	1058.2	22.3	12	60	72	208	1251.