Oilfield Research Laboratories

GENERAL INFORMATION & SUMMARY

Company Associates Oil and Gas Lease Finley Well No. 1

Location –

Section 31 Twp. 26S Rge. 17E County Woodson State Kansas

Name of Sand	Bartlesville
Top of Core	950.0
Bottom of Core	961.4
Top of Sand	950.0
Bottom of Sand	961.4
Total Feet of Permeable Sand	10.3
Total Feet of Floodable Sand	

Distribution of Permeable Sand: Permeability Range Millidarcys	Feet	Cum. Ft.
0 - 2	1.2	1.2
15 - 35	2.0	3.2
60 - 100	4.5	7.7
110 & Above	2.6	10.3

Average Permeability Millidarcys	69.3
Average Percent Porosity	18.4
Average Percent Oil Saturation	30.7
Average Percent Water Saturation	50.0
Average Oil Content, Bbls./A. Ft.	459.
Total Oil Content, Bbls./Acre	5,229.
Average Percent Oil Recovery by Laboratory Flooding Tests	
Average Oil Recovery by Laboratory Flooding Tests, Bbls./A. Ft.	
Total Oil Recovery by Laboratory Flooding Tests, Bbls./Acre	
Total Calculated Oil Recovery, Bbls./Acre	
Packer Setting, Feet	
Viscosity, Centipoises @	
A. P. I. Gravity, degrees @ 60 °F	
Elevation, Feet	