

3 023101

CANCELED - 4/10/2025 djc - per Todd Bryant This
plugging record was recorded on incorrect well and API#.

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6279

Operator: PATRICK DEV., CORP.

Name & 3408 W. 93 RD.

Address LEAWOOD, KS. 66206

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 09:00A.M. Day: 21 Month: 6 2006

Plugging proposal received from: MIKE WIMSETT

Company Name: W & W PRODUCTION CO. Phone: 620-431-4137

Were: PROBABLY, THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO APPROXIMATELY

850' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE 2" PARTED AT APPROXIMATELY 300'

AND THE TOP 300' OF 2" COLLAPSED DOWN THE WELL. THE PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐ Technician ☐ None ☐

Operations Completed: Hour: 11:00A.M. Day: 21 Month: 6 2006

Actual Plugging Report: A 7" SWEDGE WAS RAN INTO THE WELL TO 250' AT THAT DEPTH

A SOLID OBSTRUCTION HALTED PROGRESS. THE SWEDGE WAS REMOVED. 1" PIPE WAS

WASHED INTO THE WELL TO 665'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. AN ESTIMATED 210 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: SPOT LOCATION VIA GPS SURVEY. WELL NO. FROM OLD LEASE MAP.

(If additional description is necessary, use BACK of this form.)

5/14/10

2010061112

I ☐ DID observe this plugging.

Signed: Clayton P. Titel

TECHNICIAN

RECEIVED

JUL 13 2006

KCC WICHITA