

19-2618E **COPY** RECEIVED
WELL RECORD STATE CORPORATION COMMISSION

Well No. 1-A Farm Middendorf Producer Energy-Vest Inc. **SEP 30 1991**
 Location _____ Sec. _____ Twp. _____
 Elevation _____ State Kansas County Allen
 Kind (Oil, Gas, Water, Dry Hole) Oil Contractor L - K Drilling Inc.
 Producing formation _____ Top _____ Bottom _____
 Shot with _____ qts. _____ from _____ to _____
 Packer Set at _____ Kind _____ Size _____
 Liner _____ from _____ to _____ Perforated from _____ to _____

LOG					
Thick- ness	Strata	Depth	Thick- ness	Strata	Depth
2	soil	2	2	ls	720
13	clay	15	2	coal	722
4	gravel	19	20	sd sh	742
26	ls	45	2	coal	744
40	sd (shaly)	85	8	sd sh	752
7	ls	92	2	coal	754
58	sh	150	25	sd sh	779
69	ls	219	19	oil sd	798
8	sh	227			
23	ls	250			
8	sh	258			
72	ls	330			
92	sd sh	422			
38	broken ls	460			
72	sd sh	532			
2	ls	534			
2	coal	536			
4	sh	540			
17	ls	557			
4	sh	561			
3	ls	564			
32	sd sh	596			
15	ls	611			
7	sh	618			
3	ls	621			
39	sd sh	660			
5	sd (shaly)	665			
39	sd sh	704			
2	coal	706			
12	sd sh	718			

Total Depth 798'
 Open Hole _____
 Casing _____ at _____
 Casing _____ at _____
 Casing _____ at _____
 Cement _____
 Tubing _____
 Rods _____
 Additional Information
Set 20' of 8" surface pipe and
cement it in.
Ran 702' of 4½" pipe with slant hole
kick off on bottom and 82' of 5½"
pipe on top for a total of 784' of
pipe in hole. Cement to top.
Set surface pipe June 12 - 1991
Ran long string June 20 - 1991
Finish well open hole July 16 - 1991

Date Completed _____ O. K. _____ Superintendent _____