

OILFIELD RESEARCH LABORATORIES

- REGISTERED ENGINEERS -

700 NORTH MISSION
OKMULGEE, OKLAHOMA
PHONE: 4444

Chanute, Kansas

536 N. HIGHLAND
CHANUTE, KANSAS
PHONE: HE 1-2650

September 6, 1962

Creek Oil & Gas Company, Inc.
P.O. Box 377
Chanute, Kansas

Gentlemen:

Attached hereto are the results of tests run on the Bartlesville Sand Cable Tool core taken from the Henrichs Lease, Well No. A-115, located in the SE $\frac{1}{4}$ of Section 22, T-26S, R-18E, Allen County, Kansas, and submitted to our laboratory on September 1, 1962.

This core was sampled and the samples sealed in cans by a representative of Oilfield Research Laboratories.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Benjamin R. Pearman
Benjamin R. Pearman

BRP:rf

5 c.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company Creek Oil & Gas Co., Inc. Lease Henrichs Well No. A-115

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1-A	812.6	22.0	38	41	79	648	71.				
1	813.1	21.3	45	42	87	744	180.				
2	814.1	19.5	48	45	93	725	428.				
3	815.1	15.1	35	60	95	410	120.				
4	816.1						168.				