

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- DONALD P. OAK
Farm- Hamm No. 251

SEC. 4 T. 26 R. 18E
SE SW NW NW
4240' N & 655' E of SW corner

Total Depth. 809
Comm. 11-13-52 Comp. 11-18-52
Shot or Treated.
Contractor. J. W. Fisher
Issued. 12-13-52

County Allen

KANSAS



Elevation. _____

Production. Input

CASING:

8" 46'
6 1/4" 623' P.
2" 786' cem w/20 sx

Figures indicate Bottom of Formations.

soil	3
clay	18
quick sand, gravel	30
shale sandy	46
sand	52
shale	57
lime	180
shale dark	187
5 BW 180-187	
lime	190
shale	195
lime	257
9 BW 245-250	
shale sandy	315
shale	374
lime shells	417
lime	425
shale	437
lime	447
shale sandy	497
sand	507
lime 40'	512
shale	516
lime	539
shale	543
lime	548
shale	581
lime 20'	598
HFW @ 598-604	
slate black	604
lime	608
shale	612
sand	617
shale	692
lime	694
shale	702
lime 2' S.L.M.	704
shale	760
shale sandy	785.70

3" rotary core cut from
785.70 to 808.90

Fluid in hole morning of
shot: 60' wtr & 20' oil

Shot: 11-19-52 Larkin Torpedo Co.
787 - 798 5" 40 qts

Morning before moving well.

making: 3/4 BW & 3.4 BO per hr.
Total Depth 809

Sand Record:

Bartlesville sand 786 - 799