

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DONALD P. OAK


FARM R. L. Works NO. 2

SEC. 5 T. 26 R. 18E
LOC. SW SE NE
750' W & 2900' N of SE cor.

TOTAL DEPTH 806
COMM. 3-6-51 COMP. 3-10-51
SHOT OR TREATED
CONTRACTOR M. G. Jenson Drlg Co.
ISSUED 4-14-51

COUNTY Allen

KANSAS



CASINO
8" 26'
6 1/4" 619' Pulled
2" 782' cem w/20 sx cement lined pipe

ELEVATION

PRODUCTION 1/4 BOPH & 5 BWPH

FIGURES INDICATE BOTTOM OF FORMATIONS

top soil	4
clay	17
gravel	22
sand rock	29
lime	35
shale	56
lime	186
4 BWPH @ 186-98	
shale	198
lime	267
shale	369
lime shells	395
shale	413
lime	418
shale	423
lime	428
shale	438
lime	450
shale	472
lime	478
shale	510
lime	517
shale	519
lime	555
lime broken	564
lime	585
lime 20' SLM	601
shale	618
lime	622
shale	704
lime 2' SLM	706
shale	778

3" rotary core cut
from 778 to 801

Fluid in hole morning
of Shot: 300' water
and 1/2 bailer of oil.

Shot: 781-86 20 qts
786-96 25 qts

Day before moving well
making: 5 BWPH & 1/4
BOPH

shale 806
Total Depth

Tops:
Bartlesville Sand 779-98