

COMPANY D. P. OAK

SEC. 5 T. 26 R. 18E

FARM Dorothy Work


NO. 1

LOC. SE SE SW

145' N 2880' W.
of SE corner

COUNTY Allen

KANSAS



TOTAL DEPTH 821'

COMM. 5-7-51

COMP. 5-18-51

SHOT OR TREATED

CONTRACTOR M. G. Jenson Drlg. Co.

ISSUED 6-2-51

CASING

8" 24'
 6 1/4" 652' P.
 2" 787' cem w/20 sxs.

ELEVATION

PRODUCTION 3 bailers oil, 2
 bailers wtr. per hr.

FIGURES INDICATE BOTTOM OF FORMATIONS

top soil	3
clay	12
gravel	18
sand rock	24
lime	40
shale	60
lime	80
shale	84
lime	112
shale	122
lime	198
shale	203
lime	206
shale	215
lime	286
shale	384
lime shells	398
shale	435
lime shells	444
shale	453
lime	460
shale	524
lime	569
shale	596
lime 20 ft. SLM	611
shale	618
lime	622
shale	713
lime 2 Ft. SLM	715
shale	770
sandy shale	821
Total depth	

Tops:

Bartlesville sand 785-813

3" rotary core from 782-817

Shot by Larkin Torpedo Co.

787-795 4" shell 20 qts.

795-810 5" shell 60 qts.

4 bailers wtr. per hour 206-215

7bailers wtr. per hr. 611-618

Water: pipe leaking Oil; no check