

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DONALD P. OAK

FARM Dorothy Work

NO. 302

SEC. 5 T. 26 R. 18E

LOC. NE NW NE SE  
2231' N, 895' W of SE corner

TOTAL DEPTH 807

COMM. 12-19-50

COMP. 12-22-50


SHOT OR TREATED

CONTRACTOR M. G. Jenson Drlg Co.

ISSUED 1-27-51

COUNTY Allen

KANSAS



CASING

8" 26'

6 3/4" 611' P.

2" 780' cem w/20 sx.

ELEVATION

PRODUCTION 1/2 gal oil per hr,  
1/2 BWPH

FIGURES INDICATE BOTTOM OF FORMATIONS

|                                |                 |
|--------------------------------|-----------------|
| top soil                       | 5               |
| gravel                         | 20              |
| lime                           | 30              |
| shale                          | 57              |
| lime                           | 92              |
| shale                          | 115             |
| lime                           | 177             |
| 3 1/2 BWPH @ 177-85            |                 |
| shale                          | 185             |
| lime                           | 227             |
| 2 BWPH @ 227-30                |                 |
| shale                          | 230             |
| lime                           | 262             |
| shale                          | 370             |
| lime                           | 390             |
| shale                          | 414             |
| lime                           | 423             |
| shale                          | 429             |
| lime                           | 440             |
| shale                          | 507             |
| lime                           | 512             |
| shale                          | 516             |
| lime                           | 548             |
| shale                          | 582             |
| lime 20' SLM                   | 597             |
| shale                          | 608             |
| lime                           | 611             |
| shale                          | 696             |
| lime 2' SLM                    | 698             |
| shale                          | 766             |
| shale sandy                    | 776             |
| 2" Rotary Core                 |                 |
| cut from 775.90' to            |                 |
| 803.90'                        |                 |
| Fluid in hole morning of shot: |                 |
| Water -1 1/2 bailers           | Oil -1/2 gallon |
| Shot: 60 qts. from 781-799     |                 |
| shale sandy                    | 807             |
| Total Depth                    |                 |

Tops:  
Bartlesville Sand 779-803