

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DONALD P. OAK

SEC. 5 T. 26 R. 18E

FARM Dorothy Work NO. 305

LOC. SE SE SW

2675' W, 330' N. of SE corner

TOTAL DEPTH 820

COMM. 1-28-50

COMP. 1-19-51

SHOT OR TREATED

CONTRACTOR Brownlee & Alcock Drilling

ISSUED 3-17-51

COUNTY Allen

KANSAS



CASING

8" 22' P.

6 1/4" 644' P.

2" 783'

ELEVATION

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

soil	10	Mudded to top with aquagel.
shale HFW	18	
lime	37	
shale	55	
sandy shale	60	
shale	68	
lime	73	
shale	85	
lime	107	
shale	123	
lime (4 bailers wtr	190	
shale per hr.)	193	
lime	275	
shale	377	
lime	381	
shale	390	
lime & shells	400	
shale	440	
lime	450	
shale	518	
lime	522	
shale	526	
lime	554	
shale	593	
lime	610	
SIM 593		
shale, HFW	613	
lime	616	
shale	699	
lime SIM	701	
shale	714	
lime	716	
shale L.	740	
shale Dk	750	
shale L	755	
shale white	762	
shale sandy	770	
Cleaned out & shot from;		
784-803 803-808		
with 80 qts.		
sandy shale	820	
Total depth		

Tops:

Bartlesville sand 780 to 810'

Drilled and cored as Winona well

No. 1, 1-28-50. Tubed with new

2" C. W. line pipe set on rag

packer at 783'. Well tubed 1-19-51