

COMPANY DONALD P. OAK

SEC. 7 T. 26 R. 18E

FARM Mathias

NO. 157

LOC. CN¹/₂ NW SE SE
1050' N, 990' W of SE corner

TOTAL DEPTH 836

COMM. 11-6-50

COMP. 11-10-50


SHOT OR TREATED

CONTRACTOR M. G. Jenson Drlg. Co.

ISSUED 11-25-50

COUNTY Allen

KANSAS



CASING

8" 23' 8"
6 1/4" 632' P
2" liner 804 1/2'

ELEVATION

PRODUCTION input

FIGURES INDICATE BOTTOM OF FORMATIONS

top soil	6	Tops:
shale	18	Bartlesville sand 804-830
gravel	20	
lime	23	Shot: Nov. 11, 1950
shale	25	806-819, 5" 50 qts.
lime	71	819-825' 4 1/2" 20 qts.
shale	92	
lime	97	day before moving well making:
shale	101	1 1/2 bailer wtr pr hr, 2 gal oil.
lime	135	New 2" line pipe set on rag
shale	148	packer @ 804 1/2' cem w/20 sx.
lime	220	
shale	225	
lime	227	
2BWPH 227-30		
shale	230	
lime	245	
4BWPH 245-48		
shale	248	
lime	304	
shale	306	
lime	308	
shale	430	
lime shells	453	
shale	458	
lime	468	
shale	481	
lime	489	
shale	535	
lime	562	
shale	564	
lime	571	
shale	609	
lime 20' SLM	627	
shale	630	
lime	634	
shale sdy	650	
shale	665	
sand	670	
shale	716	
lime 2' SLM	718	
shale	738	
lime	740	
shale	786	
2" rotary core cut from 785.70 to		
838.60' Fluid in hole morning of		
shot: 2 3/4 bailers wtr pr hr, show oil.		
shale	836	
Total depth		