



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

February 19, 1982

Hazlett Oil Company
c/o John Siddall
RR #3, Box 13
Chanute, Kansas 66720

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Beach Lease, Well No. T-7, located in Section 24, T-26S, R-18E, in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on February 17, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/pdc

4 c to Chanute, Kansas
1 c to Topeka, Kansas

OILFIELD RESEARCH LABORATORIES

LOG

Name Hazlett Oil Company Lease Beach Well No. T-7

<u>Depth Interval, Feet</u>	<u>Description</u>
	<u>LOWER BARTLESVILLE SAND</u>
910.0 - 913.4	Brown sandstone with scattered fine shale partings.
913.4 - 915.0	Brown sandstone.
915.0 - 915.5	Gray and brown laminated shale and sandstone.

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Hazlett Oil Company Lease Beach Well No. T-7

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbla. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	910.5	18.0	31	53	84	433	12.
2	911.6	19.1	36	47	83	533	18.
3	912.5	19.2	31	46	77	462	26.
4	913.5	20.1	37	45	82	577	41.
5	914.6	19.8	32	45	77	492	15.
6	915.4	18.9	34	42	76	499	10.