

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA, BRANCHSEP
P/API No. 15 — 001 — 24,164
County Number

Operator

Shalae Oil Production

Address

2400 N. Woodlawn Wichita, Kansas 66720

Well No.

Lease Name

#4

Frevele "D"

Footage Location

660' feet from (N) (S) line

495' feet from (E) (W) line

Principal Contractor

Geologist

Mokat Drilling

Jr.

Spud Date

Date Completed

Total Depth

P.B.T.D.

3/3/81

890'

Sectional Deviation


Oil and/or Gas Purchaser

Square Deal

S. 3 T. 26 R. 18 E

Loc. 660' NSL, 495' EWL, E/2,
NE/4, SE/4

County Allen

640 Acres
N

Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 3/4"	7"	9 lbs.	125	Portland	10	None
Casing	6 1/4"	2"	4 lbs.	871'	Portland	99	Gel
Pumping String 2"		1"	1.9 lbs.	817'			

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			13 holes	1 11/16 glass	821-827
TUBING RECORD					
	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Water and sand, 10/20, 20/40	
30 sacks, 20/40, 90 sacks, 10/20.	

Type Log Run: Gamma Ray INITIAL PRODUCTION

Neutron

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

DATE OF PRODUCTION 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Air Drilling
Specialist
Oil and Gas Wells

MOKAT DRILLING

Office Phone (316) 873377 or 879-21

P.O. Box 267
Caney, Kansas 67333

Operator
Shalae Oil Co.

Well No.

Lease

Loc.

Frevele

Sec. 3

Twp 21

Rge. 18

County

State

Type/Well

Depth

Hours

Date Started

Date Completed

Allen

Ks.

Oil

890

APR 15 1981

3-3-81

Job No.	Casing Used	Bit Record						Coring Record					
		Bit No.	Type	Size	From	To	Bit No.	Type	Size	From	To	% Rec.	
Driller	Cement Used												
Driller	Rig No.												
Jearld Smith	3												
Driller	Hammer No.												

Formation Record

From	To	Formation	From	To	Formation	From	To	Formation	From	To	Formation
0	22	overborden			T.D. 890						
22	56	lime									
56	89	sandy shale									
89	193	sand-lime									
193	208	sandy shale									
208	224	lime									
224	239	sandy shale									
239	278	lime									
278	306	sand-shale									
306	423	grayshale									
423	438	sand (free oil)									
438	463	sand-shale									
463	561	lime-shale									
561	663	lime-sand									
663	689	sand-sandy shale									
689	813	Dark shale									
813	816	sand-shale									
816	818	grayshale (oil)									
818	833	sand									
833	890	sandy shale									

3-26-18e
SEP