

Dietrich Farm
Well No. 30

State of Kansas
Allen County
Northwest Quarter of Northwest Quarter
Section 22-26-18
740 feet from West Line
910 feet from North Line
Commenced spudding October 1, 1957
Finished drilling October 10, 1957

Thickness of Strata	Formation	Total Depth	Remarks
2	Soil	2	20 ft. of 8 1/2" Drive Pipe.
23	Lime	25	
15	Shale	40	
25	Lime	65	
30	Shale	95	
115	Lime	210	
2	Shale	212	
29	Lime	241	
2 Slate		243	
27	Lime	270	
90	Shale	360	280 ft. of 7" pipe
15	Lime	375	
35	Shale	410	
46	Lime	456	
5	Shale	461	
10	Sand	471	30 ft.
10	Shale	481	
9	Sand	490	
25	Shale	515	
37	Lime	552	
30	Shale	582	
19	Lime	601	
4	Slate	605	
6	Lime	611	
3	Slate	614	
5	Sand	619	40 ft.
49	Shale	668	
5	Lime	673	
25	Shale	698	
2	Lime	700	
25	Shale	725	
2	Lime	727	
32	Shale	759	
5	Oil Sand	764	
5	Oil Sand	769	
17	Dark Shale	786	20 ft.
5	Broken Sand?	791	
7	Oil Sand	798	
6	Oil Sand	804	
6	Oil Sand	810	
5	Oil Sand	815	
6	Oil Sand	821	
6	Oil Sand	827	
Total Depth		827'	

1 - 6 1/2" Robinson Packer (Gone) set at 801'
1 - 2" Sealing Wipac set at 801'
15 bags of Cement run on packer

Material used in hole

8 1/2" Drive Pipe	30'
2" Tubing	538'
1" Tubing	825'
1 - 6 1/2" Robinson Case Packer	
1 - 2" Sealing Wipac	
1 - 2" Casing	
1 - 2" Working Casing	

804'

Good Showing.
"errate 759'-764"

Showing.
Good Show. Brown Sand.
Good Show. Brown Adm Sand.
Good Show. Brown Sand.
Good Show. Brown Sand.
Good Show. Brown Sand.
Good Show. Dark Sand.