

Squire Farm
Oil Well No. 58

State of Kansas
Allen County
Section 21-26-18
Southwest quarter Northwest quarter
1270' from south line of quarter section
1135' from west line of quarter section
Commenced spudding November 10, 1958
Finished drilling November 15, 1958

Thickness of Strata	Formation	Total Depth	Remarks
25	Soil	25	35' 8 1/2" pipe water
5	Gravel	30	
15	Lime	45	
5	Shale	50	
2	Lime	52	
28	Shale	80	6-5/8" pipe run @ 305'
5	Lime	85	
17	Shale	102	
84	Lime	186	
4	Blk Shale	190	
4	Blk Shale	194	
21	Lime	215	
3	Blk Shale	218	
30	Lime	248	
3	Blk Shale	251	
33	Lime	284	
114	Shale	398	
37	Lime	435	
5	Shale	440	
10	Sand	450	
90	Shale	500	Water
42	Lime	542	
31	Shale	573	
17	Lime	590	
4	Blk Shale	594	
5	Lime	599	S.L.N. 759' Hole 2' long Poor sand - Oil small No show
97	Shale	696	
2	Lime	698	
64	Shale	762	
7	Oil-Sand	769	
3	Dark Sand	772	
Total depth		772	

1-6 1/2" Clayton Packer set @ 762'
1-2" Seating Nipple set @ 760'
20 Sacks cement run on packer

-Material Used in Hole-

8 1/2" Drive Pipe 35'
2" Tubing 774'
1" Tubing 769'
1-6 1/2" Clayton Packer
1-2" Seating Nipple
1-2" Casing
1-2" Perforation
1-2" Working Barrel

43