

Puckett Farm
Well No. ~~W-29~~ 6

State of Kansas
Allen County
Southeast Quarter of Northwest Quarter
Section 21-25-18
75' from East Line of quarter section
730' from South Line of quarter section
Commenced spudding December 12, 1959
Finished drilling December 18, 1959

<u>Thickness of Strata</u>	<u>Formation</u>	<u>Total Depth</u>	<u>Remarks</u>
4	Soil	4	
28	Clay-Sand	32	
4	Gravel	36	
9	Shale	45	8" drive pipe set @ 39'
8	Lime	53	
44	Shale	97	
99	Lime	196	
4	Shale	200	Water hole full
44	Lime	244	
4	Shale	248	
34	Lime	282	
118	Shale	400	7" pipe set @ 300'
13	Slate	413	
27	Lime	440	
65	Shale	505	
37	Lime	542	
38	Sandy Shale	580	
17	Lime	597	
1	Blk Shale	602	
5	Lime	607	5'
95	Shale	702	
2	Lime	704	
65	Shale	769	
8	Oil Sand	777	Good oil showing (free oil)
Total Depth		777	

4 7/8" packer set @ 769'
Seating nipple set @ 764'
7 sacks of cement on top of packer

Material Used in Hole

39' of 8" drive pipe
779' of 2" tubing
774' of 1" tubing
1-4 7/8" Packer
1-2" Seating nipple
1-2" Casing
1-2" Perforation
1-2" Working barrel

Fig 4