

WELL RECORD

PROPERTY OF Kenneth C. Keas
Record of Well No. Squire #51 Farm
Location SW/4 680'WEL and 440'NSL

Sec. 16 Twp. 26S Range 18E County Allen State Kansas
Rig Commenced January 11, 1966 Rig Completed January 14, 1966
Rig Contractor K-K Drilling Company
Drilling Commenced Rig 2 Drilling Completed
Contractor Price per foot \$

CASING AND TUBING RECORD

SIZE	FEET	MAKE	SIZE	FEET	MAKE
20 in.					
Conductor 15½ in.			6¼ in.		
12 in.					
10 in.			5 3/16 in.		
8¼ in.			4 7/8 in.		
6⅝ in.					

Water Well_____ft. depth, Casing_____ft

NAME OF SANDS	TOP	BOTTOM	FEET OF SAND	INITIAL TORPEDO	
				Quarts	Date of Shot
Total Depth		954			

Record of Sand and Oil Showing

How Tubed....., Plugged.....

Production first 24 hours.

Details of shot.

County _____ Recorded _____

Sec. _____ Twp. _____ R. _____

[illegible]

Well Log
 Squire #51
 SW SE SW 16-26-18E
 Allen County, Kansas

5	dirt and clay	5	
10	shale	15	
20	lime	35	
58	shale	93	
5	lime	98	
16	shale	114	
184	lime	298	
128	shale	426	
10	lime	436	
36	shale	472	
5	lime	477	
31	shale	508	
6	lime	514	
5	shale	519	
35	lime	554	
26	shale	580	
31	lime	611	
10	shale	621	little sand & odor
5	lime	626	
33	shale	659	
3	sand	662	bleeding oil
3	broken sand	665	
26	shale	691	
5	lime	696	
8	shale	704	
20	lime	724	
47	shale	771	
6	sand	777	
55	shale	832	
51	lime	883	
56	shale	939	
15	sand	954	

Squire No. 51. 1-13-66

6 1/4 rotary hole

cored from 659-681 = 768-782-903-953

set 798' of used 2" 3 1/2 line pipe

6" seating nipple at 766

centralizer on seating nipple an 1

on 3-6-9 ft up from seating nipple

3" arrow float shoe on bottom of pipe

1-14-66

cemented to top by Consolidated
Well Service used 1090 jell an 8 sack
of neat cement on bottom

1-18-66

Perforated by Ennis Perforators Inc
with 5 shots from 723-727

1-19-66

Fracped by Consolidated Well Service
broke down at 850 treated from
900-1300 closed in at 400 lbs,
used 25 sack of sand + 25 gal of acid
100 bbl. of salt water, well is
being hooped up to pump.