



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

July 23, 1980

Siddeg Energy, Ltd.
217 South Plummer
Chanute, Kansas 66720

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Finney-Leitcvach Lease, Well No. 1, located 165' East of West Line and 2,055' from the North Line, in Section 10, T-26S, R-18E, Allen County, Kansas.

The core was sampled by a representative of Oilfield Research Laboratories and submitted to our laboratory on July 11, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/tem

5 c to Chanute, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName Siddeg Energy, Ltd. Lease Finney-Leitcvach Well No. 1Depth Interval,
FeetDescriptionBARTLESVILLE SAND

780.0 - 781.1	Brown sandstone.
781.1 - 782.9	Brown slightly carbonaceous very shaly sandstone.
782.9 - 784.2	Brown very shaly sandstone.
784.2 - 790.3	Gray sandy shale.
790.3 - 793.2	Brown very shaly sandstone.
793.2 - 800.0	Gray shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Siddeg Energy, Ltd. Lease Finney-Leitcvach Well No. 1

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	780.5	16.5	46	25	71	589	10.
2	781.6	15.9	61	18	79	752	0.27
3	782.5	15.7	60	21	81	731	0.27
4	783.6	13.7	43	40	83	457	Imp.
5	790.5	11.7	20	62	82	182	Imp.
6	791.5	15.3	35	34	69	415	0.24
7	792.4	15.5	34	43	77	409	Imp.