



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

July 7, 1982

L. W. W. Oil Company
P.O. Box 223
Yates Center, Kansas 66783

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Wayne Klotzbach Lease, Well No. 2, located 165' from the North Line, and 165' from the East Line, in Section 9, T-26S, R-19E, in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on July 3, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/dlb

5 c to Yates Center, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName L. W. W. Oil Company Lease Wayne Klotzbach Well No. 2

<u>Depth Interval, Feet</u>	<u>Description</u>
---------------------------------	--------------------

BARTLESVILLE SAND

878.0 - 880.8	Dark brown sandstone.
---------------	-----------------------

880.8 - 881.8	Brownish black slightly carbonaceous slightly shaly sandstone.
---------------	---

881.8 - 883.0	Brownish black slightly carbonaceous shaly sandstone.
---------------	---

883.0 - 883.6	Gray shale.
---------------	-------------

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company L.W.W. Oil Company Lease Wayne Klotzbach Well No. 2

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbla. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	878.5	22.7	57	16	73	1004	21.
2	879.8	23.1	59	11	70	1057	22.
3	880.2	21.4	58	13	71	963	14.
4	881.4	21.1	54	21	75	884	6.8
5	882.3	20.4	60	20	80	950	2.8