

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F _____ Letter requesting confidentiality attached.

C _____ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 6637

EXPIRATION DATE _____

OPERATOR Petrocor

API NO. 15-001-26484

ADDRESS 8216 Skyline Dr.

COUNTY Allen

L. A., Ca. 90046

FIELD Gideon Oil Farm

** CONTACT PERSON Wayne Combes

PROD. FORMATION _____

PHONE 316-473-2800

PURCHASER _____

LEASE Combes

ADDRESS _____

WELL NO. #4

WELL LOCATION SE $\frac{1}{4}$

DRILLING V W & B Drilling Co.

1503 Ft. from S Line and

CONTRACTOR

713 Ft. from E Line of (E)
the SE $\frac{1}{4}$ (Qtr.) SEC 5 TWP 26 RGE 19 (W).

ADDRESS P. O. Box 7; N. Hwy 169

Cherryvale, Kans. 67335

PLUGGING Same

WELL PLAT

(Office
Use Only)

CONTRACTOR

ADDRESS _____

KCC _____

KGS _____

SWD/REP _____

PLG. _____

NGPA _____

TOTAL DEPTH 862' PBTB NONE

SPUD DATE 7-14-83 DATE COMPLETED 7-20-83

ELEV: GR _____ DF _____ KB _____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE NONE.

Amount of surface pipe set and cemented 20' DV Tool Used? NO.

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas,
Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-
completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL
AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

_____, being of lawful age, hereby certifies
that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.
The statements and allegations contained therein are true and correct.

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this _____ day of _____,

19____.

(NOTARY PUBLIC)

MY COMMISSION EXPIRES: _____

** The person who can be reached by phone regarding any questions concerning this
information.

OPERATOR PetrocorLEASE CombesSEC. 5 TWP. 26 RGE. 19 ~~XX~~

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 4

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
X Check if no Drill Stem Tests Run.				
Check if samples sent to Geological Survey				
Top Soil	0	1		
Yellow Clay	1	4		
Limestone	4	29		
Gry Shale	29'	50		
Limestone	50	60		
Gray Shale	60	103		
Limestone Shale Breaks	103	265		
Sandstone	265	273		
Siltstone	273	331		
Silty Gray Shale	331	373		
Gray Shale	373	384		
Limestone Shale Breaks	384	480		
Gray Shale	480	533		
Limestone Pawnee	533	537		
Gray Shale	537	540		
Limestone Shale Breaks	540	574		
Gray Shale	574	610		
Limestone Oswego	610	626		
Dk Gray Shale	626	633		
Limestone Ft. Scott	633	636		
Dk Gray Shale	636	641		
Silty Gray Shale	641	662		
Gray Shale	662	715		
Calcareous Gray Shale	715	726		
Limestone Ardmore	726	728		
Dk Gray Shale	728	749		
Coal	749	750		
Limestone	750	752		
Gray Shale	752	777		
Sandstone Show of Oil	777	780		
Siltstone	780	781		
Sandstone & Silty Gray Shale	781	782		
Silty Gray Shale	782	808		
Limestone	808	809		
Streak of Coal				

If additional space is needed use Page 2,

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10"	7"	15#	20'	Portland	5	NONE

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Pecker set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated production -I.P.	Gas	Water %
of gas (vented, used on lease or sold)	bbls. MCF	bbls. CFPB
		Perforations

OPERATOR

Petrocor

LEASE NAME Combes

ACO-1 WELL HISTORY

SEC. 5 TWP. 26 RGE. 19

(E)
XX
XX

FILL IN WELL LOG AS REQUIRED: WELL NO. 4

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Silty Gray Shale	809	810		
Sandstone Show of Oil	810	823		
Gray Shale	823	835		
Red Shale	835	838		
Gray Shale	838	845		
Silty Gray Shale	845	852		
Sandstone & Shale Smell of oil	852	861		
Gray Shale	861	862		
Bottom of hole	862			