

4-26-2E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- EMIL B. KUCERA
Farm- Korber No. 1

SEC. 4 T. 26 R. 2E
SE SE NW

Total Depth. 2924'
Comm. 1-23-61 Comp. 1-31-61
Shot or Treated.
Contractor. Gearhart-Canaday Drig.
Issued. 4-22-61

County Sedgwick
KANSAS



CASING:
8 5/8" 157' cem w/100 sx.
4 1/2" 2916' cem w/75 sx.

Elevation. 1404' RB

Production. 22 BOPD

Figures Indicate Bottom of Formations.

soil	25
lime & shale	100
lime	250
lime & shale	420
lime	465
shale & lime	665
shale lime	954
shale & shells	1200
shale	1430
lime	1530
lime shale	1630
lime	1670
lime shale	1705
shale & lime	1820
lime & shale	2050
sand	2150
lime	2205
shale & lime	2456
lime	2620
lime shale	2660
shale & lime	2755
lime & shale	2920
sand	2924
Total Depth	

TOPS: SCOUT	
Kansas City	2464
Burgess	2915