

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location SE SW SW

330' SL 990' WL SW

FELDERING RECORDED.

Sec 11 T. 26 R. 2E.

Casing Record.

10" 2250 Farm. H. Erdwien

No. 1

County. Sedgwick.

20" 8" 2855 Company. Aylward-Shell

15 1/2" 205 65/8" Contr. J. A. Aylward

12 1/2" 1392 53/16" Comm. 2-3-33

Comp. 3-1-33

Total Depth. 3300' Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued.

1-5-46

Pump 161 B.O. & 30W. 5 Hr. 24.3376

Formation	Depth	Formation	Depth	Formation	Depth
surface clay	60	sdv lime 6 BW	1015	slate	1930
sdv shale HFW	65	red rock	1020	lime	1935
slate	80	slate	1060	slate	1965
lime	95	lime	1070	lime	1975
slate	110	slate	1075	slate	2050
lime	120	red rock	1080	lime	2070
slate	165	slate	1100	slate	2075
lime	175	lime	1105	red rock	2080
sdv shale	185	slate	1110	slate	2095
slate	190	lime	1125	slate	2100
slate	220	slate	1145	lime	2130
lime	255	lime	1150	slate	2190
slate	265	slate	1180	lime	2200
red rock	280	lime	1165	slate	2203
lime	285	slate	1170	lime	2230
lime	320	lime	1180	lime	2240
slate	325	slate	1185	slate	2245
lime	420	lime	1195	lime	2280
slate	455	slate	1205	lime	2290
slate	460	lime	1220	slate	2305
lime	465	slate	1235	lime	2335
slate	475	lime	1245	slate	2355
lime	500	lime	1260	slate and shells	2400
slate	505	slate	1265	lime	2425
lime	525	lime	1275	slate	2430
red rock	530	slate	1350	slate	2440
lime	550	lime	1355	lime 5 BWPH2465-752525	2525
slate	560	slate	1365	lime	2570
lime	590	sdv lime	1390	slate	2630
slate	595	HFW 1360-90		lime	2635
lime	600	lime	1392	slate	2640
lime	620	lime	1398	lime	2645
slate	625	slate	1402	slate	2660
lime	635	lime	1410	slate	2705
slate	640	lime	1415	lime	2765
lime	670	slate	1420	slate	2770
lime	715	lime 1/2 bailer	1435	lime	2775
slate	725	slate	1450	slate	2780
slate	730	lime	1475	lime	2795
lime	745	slate	1485	slate	2808
slate	750	slate	1495	lime	2816
lime	755	lime	1635	slate	2825
shale	765	slate	1500	V.C. shale	2840
lime	795	lime	1585	V.C. shale	2847
slate	800	slate	1595	lime soft	2850
lime	820	lime	1620	chat	2855
lime	835	slate	1640	Top of chat 2850	
slate	840	slate	1650	broken lime	2869
lime	855	lime	1665	chat	2876 TD
slate	865	slate	1675	show oil 2870-76	
lime	870	lime	1690	Hole full fluid in 8 hrs.	
slate	890	slate	1700	with at least 200' water.	
lime	900	lime	1730	Started swabbing 12:50 PM	
slate	910	slate and shells	1760	1st hr swabbed 8 times got 96B	
slate	920	lime	1805	oil and Lowered fluid level	
lime	930	slate	1810	from 350' from top to 1350' from	
red rock	940	lime	1845	top Swab 618 B.O. and 128 Wtr	
slate	945	slate	1850	Est.	
lime	960	lime	1870	3-5-33 Pump 129 O. 85 Wtr 4 H.	
lime	970	slate	1875	3-6-33 Pump 161 O. 26 Wtr 4 H.	
slate	990	lime	1895		
slate	1000	slate	1915		

OVER

DEEPENING RECORD:

Aylward & Shell. No.1 H. Erdwein

SE SW SW of Sec. 11-26-2E.
Sedgwick County

O.T.D. 2876
 Comm. 9-16-33 Comp. 9-26-33
 Prod. 505 BO, no est. on wtr
 in 24 hrs, pmpd

chat 2910
 lime 2937
 lime sdy 2950
 lime 3118
 shale 3150
 shale 3164
 lime 3166

800' oil in 1 hr 3164-66

Total Depth.

Tops: Kinderhook 3115
 Trenton 3164

9-27-33 Pmpd 180 Bbls in 17
 hrs end 7 A.M.

7-hr test from 12 midnite to
 7 A.M. pmpd 45 BO, no trace
 of wtr

Acidized w/500 Gals. thru csg.

10-1-33 pmpd 580 BO, 6% wtr
 in 17 hrs

10-2-33 pmp 815 BO & est. 140
 wtr in 24 hrs

10-3-33 pmp 535 BO, no est.
 on wtr in 21 hrs

10-4-33 pmp 505 oil, no est.
 on wtr in 24 hrs

8 5/8 2855.

7" 3075

DEEPENING RECORD:

Comm. - 12-31-41

Comp. - 2-4-42

I. P. - Completed as
 min. well.
 Did not take
 Pot. test.

lime 3166-3240

sand 3257

shale 3271

3271 = 3263 SLC

shale sdy 3263-3275

shale 3281

shale green 3298

sand 3308

dolomite 3309

Total Depth

Pmpd 48 BO & 14 BW 24 hrs.