


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Weiskirch No. 5

SEC. 11 T. 26 R. 2E
SW SE SE

Total Depth. 4011
Comm. 6-25-55 Comp. 7-12-55
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 10-22-55

County Sedgwick
KANSAS



Elevation. 1355 KB

Production. SWDW

CASING:

8 5/8 @ 82' w/ 40 sx cmt.
4 1/2 @ 3375' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

lime	130
lime & shale	400
lime	595
lime & shale	615
shale & shells	1542
shale & lime shells	1720
shale & shells	1950
lime & shale	2877
lime	2879
chat	2975
lime	3072
lime & shale	3267
sand, shale & lime	3315
lime	4011
Total Depth	

TOPS:	
Kansas City	2384
Mississippi lime	2834
Mississippi chat	2872
Viola	3158
Simpson	3213
Arbuckle	3309
Granite	4010

DST #1: 2871-79, open 40 min. SI 20
min. rec. 8' mud, BHP 630#

DST #2: 3158-63, open 1 hr. SI 20
min. rec. 1000' fluid (35' oil, 965'
SW) IFP 0#, FFP 450#, BHP 1155#