


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
 Farm- Welskirch No. 7

SEC. 11 T. 26 R. 2E
 SE SE SE

Total Depth. 2893'
 Comm. 12-11-56 Comp. 12-18-56
 Shot or Treated.
 Contractor. Red Drilling Company
 Issued. 4-6-57

County Sedgwick
 KANSAS



Elevation. 1367' DF

Production. 25 Bbls

CASING:

8 5/8" 2108' w/95 sx cem.
 5 1/2" 2879' w/50 sx cem.

Figures indicate Bottom of Formations.

surface soil	
& clay	30
sand & shale	70
lime & shale	689
shale & shells	1377
shale & lime	2080
shale	2195
lime & shale	2520
lime	2560
shale	2650
lime	2887 RTD
lime	2893
Total Depth	

TOPS	
Lansing	2190
Kansas City	2400
Base/Kansas City	2558
Weathered Chert	2850
Mississippi	2883

DRILL STEM TEST

DST 2880-2887 120' Oil
 & Gas cut mud. 120' of
 Gas. BHP 730# 20 min.