


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILG. CO.
Farm- Weiskirch No. 10

SEC. 11 T. 26 R. 2E
NE NW SE

Total Depth. 2910'
Comm. 5-4-59 Comp. 5-10-59
Shot or Treated.
Contractor. Murfin Drilg. Co.
Issued. 7-11-59

County Sedgwick
KANSAS



CASING:
8 5/8" 156' w/110 sx cem.

Elevation. 1360' DF

Production. DRY

Figures indicate Bottom of Formations.

shale	60
lime, gyp	154
lime, shale	430
lime	580
shale, lime	720
shale, shells	1440
lime, shale	2500
lime	2567
shale, lime	2815
lime	2910
Total Depth	

TOPS: Geol.
Lansing 2185
Kansas City lime 2392
B/Kansas City 2559
Mississippi lime 2845
Chat 2878

DST #1 - 2845-60 Open 30 mins.
Weak blow 5 min. Rec. 5' mud
w/scum of heavy blk oil. IHP
120#/20 min. IF 0#, FF 20#.

DST #2 2876-84 Open 1½ hrs.
Medium blow. Rec. 150' gas,
30' muddy oil, 60' oil cut
wtr. IF 20#. FF 140#. BHP 440#.
30 min..

DST #3 2878 - 2910 Open 45 min.
Strong blow. Rec. 150' gas, 30'
OCM, 900' slightly oil & gas cut
salt wtr. IF 130#, FF 435#. BHP
460#/20 min.