


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.
Farm: ~~X~~ Delbridge No. 1.

SEC. 28 T. 26 R. 2 E
NWc NE
330' FWL 330' FWL NE $\frac{1}{4}$

Total Depth. 3563
Comm. 5-9-46 Comp. 5-27-46
Shot or Treated.
Contractor. Kiowa Drlg. Co.
Issued. 6-29-46

County. Sedgwick
KANSAS



CASING:
10 3/4" 198' LI Com.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface, clay & sand 35
gyp & clay 90
shale & lime 190
lime & shale 220
shale & sand 250
lime 570
shale 590
lime & shale 1110
shale & shells 1280
shale 1400
shale & lime 1540
lime brkn 1662
shale & lime 1975
shale 2095
shale & shells 2143
lime 2190
lime & shale lg t 2280
lime 2500
shale 2325
lime 2340
shale & lime strks 2405
shale 2570
lime 2770
shale & little lime 2870
lime 2900
shale 2945
chert 2968
Miss. lime hrd 2995
shale & chert 3015
lime & chert 3069
lime & shale 3088
shale & chert 3098
shale 3105
lime hrd 3118
lime sdy & shale 3140
lime & shale 3172
shale 3198
shale & lime 3208
shale 3286
Viola 3506
shale & lime 3344
sand 3364
shale 3530
lime & shale 3406
shale 3414
lime 3450
lime-little shale 3498
lime sdy 3550
lime 3563
Total Depth

Tops:
Kans. City Lime 2494
Miss. 2944
Chattanooga 3230
Maquokata 3282
Viola 3306
Simpson 3352
Arbuckle 3408

Run Drill Stem Test, set
packer at 2945 - opened
1 hr., rec. 150' fluid -
60' oil cut mud and 90'
salt water.

Run Schlumberger Survey at
200' to 3563'

Handwritten notes:
2945
3000
3000
3000