

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


28-26-2E

Company- OKMAR OIL COMPANY
Farm- Stranelberg No. 1

SEC. 28 T. 26 R. 2E
NW NW SE

Total Depth. 2965
Comm. 9-9-56 Comp. 9-18-56
Shot or Treated.
Contractor. Bedell-Catt Drlg Co., Inc.
Issued. 10-6-56

County Sedgwick
KANSAS



CASING:

8 5/8" 98' cem w/114 sx.

Elevation. 1389 DF

Production. Dry

Figures Indicate Bottom of Formations

surface hole	98
lime	100
lime, shale	710
shale, shells	1020
lime, shale	2235
lime	2370
lime, shale	2570
lime K. C.	2637
lime, shale	2924
chert Miss.	2926
chert, lime	2953
lime	2965
Total Depth	

Tops: KB Meas.

Kansas City	2467
Base Kansas City	2635
Probably Pleasanton	2635
Probable top Marmaton	2697
Possibly Cherokee	2893
Mississippi	2922

No show 2497-2525; 2534-50; 2574-84

Possible trace stain.

No free oil, No odor 2616-22

No Show 2624-35

Some free oil heavy brown,

Fair stain, no odor 2922-24

No Show 2924-25

Slight trace free oil.

Slight stain. No odor 2925-31

No show 2931-33; 2950-61

Ran DST: 2914-26 Open 1 hr.,

Rec. 55' mud w/a very slight
trace of oil at top. BHP 870 psi.
(30 minst)

Took no cores

Ran Schlumberger E-S log -
No microlog.