

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


Company - JOHN P. GATY
Farm - Coleman No. 1

SEC. 32 T. 26 R. 2E
SW NE NW

Total Depth. 3008
Comm. 3-18-50 Comp. 4-30-50
Shot or Treated.
Contractor. Max Howell
Issued. 5-20-50

County. Sedgwick

KANSAS



Elevation. _____

Production. Dry

CASING:
10" 1603
8" 2440
7" 2670
5 1/2" 2982 1/2"

Figures Indicate Bottom of Formations.

cellar	8	lime	890	shale	1720
clay	25	shale	900	lime	1730
blue mud	50	lime	937	shale	1735
shale	110	shale blk	942	lime	1745
lime	125	lime	960	shale	1780
shale shells	155	shale	975	lime	1795
lime	170	lime	985	shale	1800
shale	195	shale	995	lime	1810
lime	200	lime	1010	shale	1815
shale	210	shale	1020	lime	1847
lime	230	lime	1027	shale	1855
shale	250	shale	1035	lime	1865
lime	260	redrock	1040	shale	1880
shale	265	shale	1055	lime	1885
lime	280	lime	1060	shale	1890
shale	305	redrock	1065	lime	1970
redrock	312	lime	1075	shale	1980
shale	335	shale brown	1085	lime	2020
lime	350	lime	1090	shale	2060
shale	380	shale	1100	shale & shells	2105
lime	420	lime brkn.	1115	shale	2160
shale	430	shale	1125	lime	2210
lime	475	lime	1145	shale	2215
lime brown	515	shale	1197	lime	2220
shale	517	lime	1203	shale	2230
lime	530	shale	1225	lime	2295
shale	540	lime	1228	lime soft	2303
lime	565	shale	1238	lime white	2340
shale	580	shale, blk	1241	lime sandy	2355
lime	600	shale	1265	lime hard	2360
shale	605	lime	1297	lime	2423
lime	620	shale	1305	shale	2430
redrock	625	lime	1335	lime	2433
lime	645	shale	1340	shale	2443
shale	655	lime	1355	lime hard & sharp	2448
lime	660	shale	1365	shale light	2460
shale	665	lime	1377	shale	2480
lime	670	shale	1395	shale sandy	2520
shale	680	lime	1410	lime KC	2664
lime	685	shale	1430	shale	2670
shale	700	lime	1525	lime	2708
redrock	705	shale	1555	shale dark	2730
lime	715	lime	1575	shale & shells	2834
shale	735	shale	1580	lime	2860
lime	745	lime	1600	shale	2865
shale	750	shale	1610	lime	2875
lime	768	lime	1638	shale	2881
shale	780	shale brown	1645	lime	2900
lime	815	lime	1652	shale & shells	2947
shale	825	shale	1660	lime	2955
lime	840	lime	1664	shale	2959
shale	845	shale blk	1675	top V.C. shale	2982 1/2
redrock	852	lime	1680	sand & shale	2984 1/2
lime	860	shale	1685	sand	3008
shale	880	lime	1710	Total depth	

Scout Tops:

Lansing	2160
KC	2520
Burgess	2959
Mississippi	3006

Water Record

$\frac{1}{2}$ bailer at 852-860
 $\frac{1}{2}$ bailer at 1905
Hole full water at 2295-2300
Hole full water at 2594-2600
1 bailer at 2994'