

14-26-2E

COPY

KANSAS DRILLERS LOG

API No. 15 _____ County _____ Number _____

S. 14 T. 26S R. 2 E

Loc. 100' N NE NE NW

County Sedgwick

Operator
VINCENT OIL CORPORATION

Address
230 O. W. GARVEY BLDG., WICHITA, KANSAS 67202


Well No. #1 Lease Name HAMANT

Footage Location
feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor White & Ellis Drlg., Inc. Geologist Dick Jordan & Larry Friend

Spud Date 5-11-80 Total Depth 3180 P.B.T.D. _____

Date Completed 7-1-80 Oil Purchaser _____



Elev.: Gr. 1381

DF _____ KB 1386

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8-5/8"		222'	Common	150	5 sx. CC
Production		5½"		3176'	Regular	100	10% Salt, 2% gel. 3/4% FRA

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2-7/8"	3153.75'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____	Producing method (flowing, pumping, gas lift, etc.) _____
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls. Gas _____ MCF Water _____ bbls. Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold) _____	Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
VINCENT OIL CORPORATION

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
OIL WELL

Well No. #1 Lease Name HAMANT

S 14 T 26 R 2 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Cellar	0	7	Lansing	2208 (- 822)
Clay	7	90	Kansas City	2411 (-1025)
Shale, Lime	90	100	Bs.K.C.	2573 (-1187)
Lime	100	165	Mississippian	2884 (-1498)
Lime, Shale	165	520	Kinderhook Sh.	3124 (-1738)
Shale, sandy lime	520	847	Hunton	3175 (-1789)
Shale, Lime	847	2890	Log. T.D.	3179 (-1793)
Lime	2890	3027		
Lime, Shale	3027	3054		
Lime	3054	3130		
Shale, Lime	3130	3180		

Drill Stem Test #1 - 2829 - 2890 ft. Misrun.

Drill Stem Test #2 - 2828-2892 ft. Open 30 min., shut in 60 min., open 30 min., shut in 60 min. Fair blow on first opening, weak blow 2nd opening. Recovered 1' free oil, 40' very slightly oil and gas cut mud, 60' slightly oil & gas cut mud, 120' heavy oil & gas cut mud. IFP 85#-130#, ISIP 820#
FFP 150#-150#, FSIP 820#

Drill Stem Test #3 - 2891-2907 ft. Open 30 min., shut in 60 min., open 45 min., shut in 60 min. Initial weak blow building to strong. Recovered 270' gas in pipe. 360' gassy oil, 90' muddy gassy oil and 90' slightly oil cut muddy salt water.
IFP 65-130#. ISIP 810#
FFP 160-200#, FSIP 800#.

Drill Stem Test #4 - 3106-3180 ft. Open 30 min., shut in 60 min., open 45 min., shut in 60 min. Strong blow on 1st & 2nd opening. Recovered 100' gas in pipe, 1680 ft. heavy oil cut mud (70% oil & 30% mud), 240 ft. salt water.
IFP 135-418#, ISIP 1158#
FFP 533-741#, FSIP 1158#.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Richard H. Diebel
Signature

Vice President
Title

July 10, 1980
Date

06/8/1

1A-20-96

14-265-2E

JUL 8 0 RECD
State Geological Survey
WICHITA BRANCH

DRILLERS LOG

OPERATOR: Vincent Oil Corp, 230 O.W. Garvey Bldg.; 200 W. Douglas; Wichita, K
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042 67202

Lease Name Hamant Well No. 1
Sec. 14 T. 26 R. 2E Spot 100' N C NE NE NW
County Sedgwick State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 222' with 150 Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Total Depth 3180' KB

Drilling Commenced: 5/10/80 Drilling Completed 5/19/80

Formation	From	To	Tops
Cellar	0	7	Mississippi - 2890
Clay	7	90	
Shale, Lime	90	100	
Lime	100	165	
Lime, Shale	165	520	
Shale, sandy lime	520	847	
Shale, Lime	847	2890	
Lime	2890	3027	
Lime, Shale	3027	3054	
Lime	3054	3130	
Shale, Lime	3130	3180	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation Perforated Interval Number Shots