

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. SW NW NW

Sec. 14 T. 26 R. 2E.

Casing Record.

13" 1401 10" 2008 Farm. Hamant
 20" 8" 2738 Company. Gypsy Oil Co.
 15 1/8" 170 65/8" Contr. Corbett and Barbour
 2 1/4" 53/16" Comm. 1-11-33 Comp. 2-17-33

County. Sedgwick.

No. 8



Elevation.

Total Depth. Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 4-22-33

749B.3 and 175B.W. 183/4 hrs. TD 2855

Formation	Depth.	Formation	Depth	Formation	Depth.
shale	65	shale	975	shale	1950
sdv lime HFW 65	85	lime	980	lime	1955
shale	90	shale	990	shale	1980
lime	100	6 BW 990-96		shale and shells	2008
shale	115	sand	996	shale	2065
lime	130	shale	1025	lime	2070
shale	140	lime	1030	shale	2085
lime	150	shale	1050	lime	2120
shale	155	lime	1065	shale	2125
lime	175	shale	1070	lime	2130
shale	200	red rock	1075	shale	2210
lime	240	lime	1110	lime	2235
shale	260	shale	1115	shale	2250
red rock	270	lime	1120	lime	2255
lime	300	shale	1155	shale	2265
shale	310	lime	1185	lime	2275
lime	320	shale	1190	lime	2330
shale	325	lime	1210	shale	2370
lime	355	shale	1215	lime	2380
shale	360	lime	1235	shale	2400
lime	380	shale	1240	lime	2440
shale	420	lime	1250	show oil 2410-15	
lime	430	shale	1280	shale	2445
shale	440	shale	1300	lime	2510
lime	460	lime	1315	5 BW 2455-85	
shale	465	shale	1330	broken lime	2535
lime	475	lime	1372	lime	2565
shale	480	HFW 72-82		shale	2620
lime	515	sand	1382	lime	2650
red rock	525	lime	1401	shale	2665
lime	530	lime	1420	lime shells	2682
shale blue	555	shale	1450	red rock	2687
lime	570	lime	1460	lime	2715
shale	580	shale	1470	shale	2738
lime	590	lime	1480	lime	2740
1/2 BW 535-40		shale	1495	<u>SAMPLE LOG</u>	
shale	600	lime	1540	lime	2780
lime	620	shale	1560	shale brown and	
shale	640	lime	1590	grey	2805
shale and shells	650	shale	1595	lime	2815
lime	665	lime	1610	Var. colored shale	2847
shale	675	shale	1620	chat	2850
lime	720	lime	1630	Halliburton line shows	
shale	725	shale	1650	2850 equals 2855 feet.	
lime	735	lime	1660	T.D.	2855
shale	745	shale	1680	Top of chat 2852 feet.	
lime	760	lime	1690	2500 feet of oil in 2 hours	
shale	770	shale	1710	from 2852 to 2855.	
lime	800	lime	1715		
shale	805	shale	1720	<u>PRODUCTION RECORD.</u>	
lime	815	lime	1745		
shale blk	840	shale	1750	2-14-33 Swab 1068 bbls oil	
lime	860	lime	1760	and 26 bbls water in 14 hrs.	
lime	870	shale	1785	fluid level 300 feet from	
shale	890	lime	1810	top when swabbing begun	
lime	900	shale	1820	could not be lowered below	
shale	925	lime 1/2 BW	1865	1400 feet from top.	
red rock	930	shale	1875		
lime	945	lime	1890	2-16-33 started to pump	
red rock	950	shale	1910	at 11 A.M. 3 inch tubing.	
lime	960	lime	1920	65/8 set 112 of 6" liner	
				at 2738 and ran to bottom.	

118202