

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE SE SW

Sec. 15 T. 26 R.2E

250' EL 1070' SL SW/4

Casing Record

County- Sedgwick

20"	10"	Farm-Wm. Brown	No. 3
15 $\frac{1}{2}$ " 88'	8 $\frac{1}{2}$ "	Company- Shell Petr. Corp.	
12 $\frac{1}{2}$ "	65/8"	Contr.- Noble & Olson	
Total Depth 2893	53/16"	Comm.- 10-14-29	Comp.- 11-11-29



Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to

Elevation

Figures Indicate Bottom of Formations.

Initial Production Sw. 224 bbls.

Date Issued. 11-30-29

oil & 121 bbls. wtr.

Formation	Depth
surface	88
shale shells	364
brkn shale lime	552
shale lime	871
shale	1040
shale lime shells	1441
brkn lime	1591
shale lime shells	1817
brkn lime shale	1973
brkn lime	1983
shale	2101
brkn lime	2141
lime	2211
brkn lime	2249
shale	2279
brkn lime	2307
lime	2426
brkn lime	2458
lime	2489
brkn lime	2524
lime	2565
shale brkn lime	2666
brkn lime	2696
shale shells	2734
brkn lime	2762
shale	2800
brkn lime shale	2871
green yellow shale	2876
shale green red	2879
lime brown	2881
shale yellow SLM	2888
lime chat blk	2889
chat	2893

Total Depth 2893

2889-91 300' oil in one hr.

2891-93 Increased to 700' 2 hrs.

2889-93 Pay 1250' oil in 6 hrs.

8 5/8" csg. 2865

7" csg. 2888

SAND RECORD:

CHAT 2889-2893

PAY 2889-2893